

Florence Regional Sewage District
6894 Log Lick Rd.
Florence, IN. 47020
(812) 427-4000
Fax (812) 427-9757
fncrsd@embarqmail.com

SUMMARY OF LATERAL INSTALLATION REQUIREMENTS

1. All houses, buildings, etc., shall connect to the District's sanitary sewer system within **90** days of notice Providing a sewer is within 300 feet of the property line. Only one building may connect to the sewer main per lateral unless otherwise approved by the District.
2. No foundation or other storm water drains shall be interconnected to the sewer lateral installed and connected to the District's sanitary sewer.
3. The existing sewer line from the building to the septic tank may only be used if it is located under a building addition, patio, porch or paved driveway. Air test is required to show if acceptable for re-use. The property owner shall bear the cost of all testing. The District inspector shall be onsite for the duration of the air test.
4. The owner or contractor shall notify the District prior to covering the installed lateral so that the District can make an inspection to determine compliance with the District's sewer use ordinance. Such notification shall be made 24 hours prior to the need for the inspection. If the inspection fails and a second inspection is required, or contractor is not on site for scheduled inspection, or fails to cancel, an additional fee of **\$25.00** will be due. This must be paid prior to the time of the follow up inspection.
5. Property owners are hereby advised that the County Board of Health regulates the operation and maintenance of private sewage disposal (septic) systems. The County ordinance provides in part that, upon connection to a public sewer, a septic tank "...shall be abandoned and filled with earthen material in a safe and sanitary manner." Please contact the appropriate County Board of Health for further information.
6. Acceptable Pipe Materials:

PVC PIPE: SCHEDULE 40, ASTM D-1785, FOUR INCH
PVC PIPE: SDR 21, ASTM D-241, FOUR INCH
GASKETS JOINTS ASTM D-3212
GASKETS ASTM F-477
FITTINGS SDR- 26
DUCTILE IRON MECHANICAL COUPLING WITH PROPER FITTINGS.
CLEAN OUTS TO BE LOCATED THREE FEET WITHIN THE FOUNDATION
AND NO MORE THAN 300 FEET APART.

7. Shut-off Gate:

Shall be installed in pipe for each new service with riser pipe extending to ground level. Valve cartridge shall be glued with PVC cement to a length of $\frac{3}{4}$ " pipe with the tee at the top.

7. Bedding:

Use fill sand or Number 8, 9 or 11 stone
Fill material is to be placed from 6 inches below to 6 inches above the pipe

The trench should be a minimum of 18 inches wide

8. Lateral shall be installed no closer than 20 feet from water wells unless PVC pressure grade pipe is used meeting SDR 21 and ASTM D-2241. Any proposed installation requiring pressure pipe shall be reviewed and accepted by the District and the District's engineer **prior to installation.**
9. Laterals shall terminate within 3 feet of the building unless the conditions in item #3 above are met.
10. Additional information on District standards and specifications may be obtained from the District's office during business hours of 7:00a.m. to 3:30p.m. Monday through Friday.

Florence Regional Sewage District
6894 Log Lick Rd.
Florence, IN. 47020
Phone: 812-427-4000 Fax: 812-427-9757

11. Septic tank effluent may be pumped into the sanitary sewer system.
12. **The District shall inspect ALL laterals.** Please call the District office at 812-427-4000, 24 hours prior to time of inspection.
13. **Contractors shall lay 14 gauge-stranded wire the entire length of the lateral.** Wire is to be placed on top of the lateral. The District inspector will verify placement of the wire. After inspection, bedding is to be placed on top.
14. Call before you dig. IUPPS 1-800-382-5544, 48 hours prior to digging.